

FlexTable: Conduit Table

Current Time: 0.000 hours														
ID	Label	Start Node	Stop Node	Length (Scaled) (m)	Catalog Class	Elevation Ground (Start) (m)	Elevation Ground (Stop) (m)	Invert (Start) (m)	Invert (Stop) (m)	Elevation Crown (Start) (m)	Elevation Crown (Stop) (m)	Slope (Calculated) (m/m)	Material	Velocity (m/s)
169-CE-71	BE-67	BE-67	44.73 <none>	32.05	32.07	30.95	30.55	31.15	30.75	8.943	Concrete	0.51		
172-CE-72	BE-68	BE-69	44.30 <none>	32.83	32.37	31.49	31.03	31.69	31.23	10.385	Concrete	0.53		
173-CE-73	BE-69	D-3	26.40 <none>	32.27	32.69	31.03	30.77	31.23	30.97	9.897	Concrete	0.53		
176-CE-74	BE-70	BE-71	47.85 <none>	32.07	32.64	31.67	31.25	31.87	31.46	8.568	Concrete	0.51		
215-CE-75	BE-73	BE-73	18.53 <none>	32.28	32.35	31.04	30.82	31.24	31.02	11.880	Concrete	0.56		
180-CE-77	BE-72	BE-72	52.71 <none>	32.07	32.15	30.55	29.80	30.75	30.00	14.185	Concrete	0.50		
183-CE-78	BE-73	BE-74	47.71 <none>	32.26	32.44	30.82	30.46	31.02	30.64	7.953	Concrete	0.46		
185-CE-79	BE-70	BE-74	44.03 <none>	32.87	32.44	31.67	31.16	31.87	31.36	11.584	Concrete	0.56		
188-CE-80	BE-74	BE-74	21.23 <none>	32.87	32.10	30.44	30.14	30.64	30.34	14.128	Concrete	0.59		
219-CE-81a	BE-70a	BE-72	5.52 <none>	32.10	32.15	30.14	29.80	30.34	30.00	61.432	Concrete	0.94		
216-CE-80	BE-71	BE-73	41.04 <none>	32.64	32.35	31.26	30.82	31.46	31.02	9.991	Concrete	0.53		
222-CE-82	BE-76	BE-66	15.51 <none>	32.02	32.05	31.10	30.95	31.30	31.15	5.433	Concrete	0.52		
Depth (Average End) / Rise (%)														
13	1.50	1.63	200.0	0.013	31.0149									
14.5	1.50	1.83	200.0	0.013	32.4252									
14.5	1.50	1.74	200.0	0.013	32.5473									
13	1.50	1.56	200.0	0.013	30.3604									
14	1.50	1.00	200.0	0.013	35.7994									
13.5	1.50	2.35	200.0	0.013	29.0629									
14.5	1.50	1.49	200.0	0.013	29.9799									
15.5	1.50	1.49	200.0	0.013	29.2529									
14	1.50	1.96	200.0	0.013	35.3010									
13.5	1.50	2.04	200.0	0.013	30.0844									
13.5	1.50	1.31	200.0	0.013	81.4244									
14.5	1.50	1.76	200.0	0.013	31.7932									
14.5	1.50	1.67	200.0	0.013	31.8511									

AIC_Exitante_Urb_Astete.stw
11/26/2015Bentley Systems, Inc. Haestad Methods Solution Center
27 Sherman Company Drive Suite 200 W. Watertown, CT 06795 USA +1-203-755-1686Bentley SewerGEMS VB (SELECTseries 3)
(06.11.03.77)
Page 1 of 1

FlexTable: Conduit Table

Current Time: 0.000 hours														
ID	Label	Start Node	Stop Node	Length (Cant) (m)	Catlog Class	Elevation Ground (Start) (m)	Elevation Ground (Stop) (m)	Invert (Start) (m)	Invert (Stop) (m)	Elevation Crown (Start) (m)	Elevation Crown (Stop) (m)	Slope (Calculated) (m/m)	Material	Velocity (m/s)
31-CE-1	BE-1	BE-2	48.78 <none>	38.86	38.38	37.34	36.82	37.94	37.02	10.660	Concrete	0.53		
32-CE-2	BE-3	BE-4	17.87 <none>	38.86	38.37	37.71	37.19	37.91	37.25	8.891	Concrete	0.51		
33-CE-3	BE-4	BE-2	50.16 <none>	38.77	38.38	37.55	36.82	37.95	37.02	10.766	Concrete	0.63		
34-CE-4	BE-5	BE-6	46.25 <none>	38.60	38.19	37.25	36.91	37.45	37.11	7.332	Concrete	0.46		
37-CE-5	BE-6	BE-4	44.60 <none>	38.60	38.19	36.82	36.35	37.02	36.50	10.538	Concrete	0.53		
39-CE-6	BE-6	BE-7	50.17 <none>	38.19	38.01	36.35	35.84	36.55	36.06	9.767	Concrete	0.53		
41-CE-7	BE-7	BE-7	46.38 <none>	38.19	38.01	36.51	35.86	36.71	36.06	6.560	Concrete	0.74		
43-CE-8	BE-7	BE-9	48.46 <none>	38.01	36.85	35.96	35.13	36.06	35.33	10.660	Concrete	0.80		
45-CE-9	BE-10	BE-10	58.17 <none>	36.85	36.85	35.13	34.32	35.33	34.52	13.824	Concrete	0.88		
48-CE-10	BE-12	BE-12	36.43 <none>	36.83	36.32	35.59	35.17	35.79	35.37	13.802	Concrete	0.59		
50-CE-11	BE-12	BE-13	22.54 <none>	36.52	36.79	35.17	34.37	35.37	34.57	14.197	Concrete	0.85		
51-CE-12	BE-16	BE-16	36.26 <none>	35.63	35.69	34.38	34.25	34.58	34.42	1.182	Concrete	0.39		
57-CE-14	BE-16	BE-17	48.47 <none>	35.69	35.73	34.22	34.19	34.42	34.38	0.619	Concrete	0.20		
58-CE-15	BE-17	BE-18	53.36 <none>	35.79	35.79	34.37	34.10	34.57	34.39	2.234	Concrete	0.36		
60-CE-16	BE-17	BE-18	46.03 <none>	35.77	35.47	34.19	33.89	34.39	34.08	6.735	Concrete	0.46		
62-CE-17	BE-18	BE-19	21.57 <none>	35.47	35.51	33.88	33.70	34.08	33.90	8.344	Concrete	0.51		
65-CE-18	BE-20	BE-20	46.31 <none>	35.41	35.01	34.62	33.90	34.62	34.10	12.523	Concrete	0.58		
66-CE-19	BE-21	BE-19	46.63 <none>	35.91	35.51	33.99	33.70	34.19	33.90	6.219	Concrete	0.44		
68-CE-20	BE-22	BE-18	45.71 <none>	35.12	35.47	34.78	33.88	34.98	34.08	19.488	Concrete	0.66		
70-CE-21	BE-10	BE-23	42.58 <none>	35.85	35.54	34.32	34.15	34.39	33.65	20.432	Concrete	1.10		
72-CE-22	BE-23	BE-24	70.13 <none>	35.54	34.51	33.45	32.89	33.65	33.05	7.885	Concrete	0.79		
73-CE-23	BE-19	BE-24	49.30 <none>	35.51	34.51	33.70	32.89	33.65	33.05	16.433	Concrete	0.63		
75-CE-24	BE-25	BE-25	49.20 <none>	34.51	33.45	32.89	31.87	33.09	32.07	20.733	Concrete	1.14		
77-CE-25	BE-26	BE-26	63.84 <none>	35.45	32.53	31.87	30.95	32.07	31.13	14.725	Concrete	1.03		
79-CE-26	BE-26	D-1	56.21 <none>	32.53	31.81	30.28	28.83	30.98	29.13	25.794	Concrete	1.61		
82-CE-27	BE-27	BE-28	62.86 <none>	31.87	30.88	31.27	31.51	31.60	31.71	25.823	Concrete	0.72		
84-CE-28	BE-28	D-2	64.68 <none>	32.27	33.03	31.60	32.10	31.71	29.220	Concrete	0.80			
91-CE-31	BE-32	BE-31	45.60 <none>	35.34	34.49	34.14	32.65	34.34	32.85	24.561	Concrete	0.80		

AIC_Exitante_Urb_Astete.stw
11/26/2015Bentley Systems, Inc. Haestad Methods Solution Center
27 Sherman Company Drive Suite 200 W. Watertown, CT 06795 USA +1-203-755-1686Bentley SewerGEMS VB (SELECTseries 3)
(06.11.03.77)
Page 1 of 6

FlexTables: Conduit Table

Current Time: 0.000 hours														
ID	Label	Start Node	Stop Node	Length (Scaled) (m)	Catalog Class	Elevation Ground (Start) (m)	Elevation Ground (Stop) (m)	Invert (Start) (m)	Invert (Stop) (m)	Elevation Crown (Start) (m)	Elevation Crown (Stop) (m)	Slope (Calculated) (m/m)	Material	Velocity (m/s)
91-CE-32	BE-31	BE-33	44.28 <none>	34.49	34.43	32.65	32.62	32.85	32.82	0.677	Concrete	0.30		
92-CE-33	BE-33	BE-34	48.84 <none>	34.43	34.21	32.62	32.49	32.82	32.69	2.705	Concrete	0.50		
93-CE-34	BE-35	BE-34	43.34 <none>	34.23	34.21	33.03	32.49	33.23	32.66	12.403	Concrete	0.56		
94-CE-35	BE-34	BE-36	51.13 <none>	34.21	34.72	32.49	32.40	32.69	32.60	1.741	Concrete	0.43		
101-CE-37	BE-37	BE-38	38.94 <none>	34.46	34.72	34.17	32.40	34.37	32.60	4.932	Concrete	0.52		
102-CE-38	BE-38	BE-39	45.46 <none>	34.42	33.79	32.46	32.45	32.46	32.46	3.981	Concrete	0.57		
103-CE-39	BE-39	BE-39	45.80 <none>	34.92	34.42	32.23	32.06	32.46	32.31	3.711	Concrete	0.57		
104-CE-40	BE-41	BE-39	38.50 <none>	34.95	34.42	33.71	33.02	33.91	33.22	17.922	Concrete	0.66		
110-CE-41	BE-39a	BE-42	44.28 <none>	34.50	34.41	32.60	32.71	33.15	32.91	4.861	Concrete	0.42		
114-CE-42	BE-42	BE-43	59.57 <none>	34.41	33.90	32.71	31.63	32.91	31.83	18.131	Concrete	0.66		
116-CE-43	BE-40	BE-44	57.12 <none>	33.79	33.55	31.88	31.38	32.13	31.63	8.794	Concrete	0.78		
117-CE-44	BE-43	BE-44	47.27 <none>	33.90	33.55	31.63	31.38	31.83	31.58	5.278	Concrete	0.42		
118-CE-45	BE-46	BE-45	53.38 <none>	33.44	33.20	32.24	31.68	32.44	31.88	10.460	Concrete	0.53		
221-CE-48a	BE-46a	BE-46	22.46 <none>	33.63	33.44	32.39	32.24	32.59	32.44	6.678	Concrete	0.46		
125-CE-49	BE-49	BE-48	10.86 <none>	33.17	33.00	31.11	30.97	31.86	31.27	13.912	Concrete	0.94		
131-CE-52	BE-49	BE-50	44.09 <none>	33.46	32.77	30.78	30.68	31.03	30.93	2.221	Concrete	0.50		
133-CE-53	BE-51	BE-49	39.01 <none>	33.44	33.46	32.13	30.78	32.35	30.69	24.699	Concrete	0.88		
136-CE-54	BE-52	BE-53	36.45 <none>	34.77	34.60	33.61	33.14	33.81	33.34	12.866	Concrete	0.58		
138-CE-55	BE-54	BE-54	43.65 <none>	34.60	34.83	33.14	33.00	33.34	33.20	3.207	Concrete	0.36		
140-CE-56	BE-54	BE-55	50.03 <none>	34.83	34.51	33.80	32.52	33.30	32.72	9.460	Concrete	0.76		
144-CE-58	BE-56	BE-57	43.84 <none>	34.21	33.91	32.24	32.01	32.44	32.21	5.241	Concrete	0.62		
146-CE-59	BE-57	BE-58	59.99 <none>	33.91	33.38	32.01	31.71	32.21	31.91	5.001	Concrete	0.61		
148-CE-60	BE-58	BE-59	45.52 <none>	33.38	32.86	31.71	31.34	31.81	31.54	8.146	Concrete	0.74		
150-CE-61	BE-59	BE-61	85.99 <none>	32.98	32.71	31.34	31.07	31.94	31.27	3.140	Concrete	0.53		
154-CE-63	BE-61	BE-63	7.69 <none>	32.75	32.71	31.07	30.99	31.17	31.19	10.390	Concrete	0.81		

AIC_Exitante_Urb_Astete.stw
11/26/2015Bentley Systems, Inc. Haestad Methods Solution Center
27 Sherman Company Drive Suite 200 W. Watertown, CT 06795 USA +1-203-755-1686Bentley SewerGEMS VB (SELECTseries 3)
(06.11.03.77)
Page 2 of 6

FlexTable: Conduit Table